

Date: Monday, 11/6/2006 2:39:16 PM  
 User: Kim Johnston

## Process Sheet

Customer	: CU-DAR001 Dart Helicopters Services	Drawing Name	: PLUG
Job Number	: 29330		
Estimate Number	: 10512		
P.O. Number	: <i>N/A</i>	Part Number	: D26511
This Issue	: 11/6/2006	S.O. No.	: <i>N/A</i>
Prsht Rev.	: NC	Drawing Number	: D2651 REV. B
First Issue	: <i>N/A</i>	Project Number	: <i>N/A</i>
Previous Run	: 29005	Drawing Revision	: B
	Type : MACHINED PARTS	Material	: <i>N/A</i>
Written By	: <i>[Signature]</i>	Due Date	: 11/24/2006
Checked & Approved By	: <i>[Signature]</i>	Qty:	300 Um: Each
Comment	: Est: A 02.04.15 New Issue NG : Est: B 05.12.12 added deburr EC		

## Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0	M6061T6R0500	6061-T6 Round Bar .500"
-----	--------------	-------------------------



Comment: Qty.: 0.0421 f(s)/Unit Total : 12.6315 f(s)  
 Material: 6061-T6 (QQ-A-225/8) 0.500" Dia  
 (M6061T6R0500)  
 Batch: *1102447*

DE 06/11/09

2.0	HARDINGE	HARDINGE CNC LATHE SMALL
-----	----------	--------------------------



Comment: HAAS CNC VERTICAL MACHINING #1  
 1- Turn as per Folio FA219 and Dwg D2651  
 2- Deburr

J.G / SP 06/11/09 3/8

3.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

J.G / SP 06/11/09

4.0	QC8	SECOND CHECK
-----	-----	--------------



Comment: SECOND CHECK

~~SP~~ ~~SP~~ SP 06/11/09 1/8316

5.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
-----	-------------	-------------------------------



Comment: SMALL & MEDIUM FAB RESOURCE 1  
 Deburr as per dwg D2651

SAD 06/11/23





3/6

PTD

BOS

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes ☒ No ☐ DQA: LD Date: 07/01/10  
 QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			
06/11/23	5	Grinded to much the end of the piece (1 scrap)	 06/10/23 07/01/10	Scrap is destroyed	SAN 06/10/23	 06/11/23	 06/10/23 07/01/10	 07/01/10

NOTE: Date & initial all entries

Date: Monday, 11/6/2006 2:39:17 PM  
User: Kim Johnston

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: PLUG

Job Number: 29330

Part Number: D26511

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: HAND FINISHING RESOURCE #1

Acid etch and Alodine as per QSI 005 4.1

R.M

06/11/29

310x

7.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3  
(Only larger section necessary)

FR / am 07/01/05

310

8.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT

FC

07 01 05

310

9.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock  
Location: FRS

FC

07 01 10

310

10.0

QC21

FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

07/01/10

Job Completion



CL07101110

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries





**DART**

DESIGN #	DRAWN BY #	<b>DART AEROSPACE LTD</b> HAWKESBURY, ONTARIO, CANADA	
CHECKED #	APPROVED #	DRAWING NO. D2651	REV. B SHEET 1 OF 1
DATE 03.12.19		TITLE PLUG	SCALE 1:1
A	97.03.25	NEW ISSUE	
B	03.12.19	ADD POWDER COAT, MS28775-008	

**RELEASED**

03.12.19

**D2651-1 PLUG:****GROOVE DETAIL (SCALE 5:1)****D2651-1 PLUG**

- 1) MATERIAL: 6061-T6 (QQ-A-225/8) OR 1100-0 (QQ-A-225/1)
- 2) FINISH: ACID ETCH & ALODINE PER DART QSI 005 4.1  
POWDER COAT WHITE (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.010 MAX

**D2651-3 O-RING**

- 1) MATERIAL: BUNA N, 70 DUROMETER  
3/16 ID, 5/16 OD, 1/16 WIDTH  
(PARKER 2-008, MS28775-008 OR EQUIVALENT)

SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 29330

**Copyright © 1997 by DART AEROSPACE LTD**

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

